
Cogwheel user guide

Cogwheel is **a Spirograph**, as two plugins for Resolume Arena and Avenue — and again as an OpenFX bundle for Resolve, Vegas, Nuke and Natron.

A toothed ring is pinned to the paper. A smaller toothed wheel rolls around inside it, in mesh, and a pen dropped through one of the wheel's holes is carried along for the ride. **Nothing here evaluates a curve.** Set the two tooth counts and the figure follows.



> **Before you rely on this:** the central claims are measured rather than asserted. The pen is walked for the full number of turns the tooth counts predict and the test fails if it does not come home; a second fails unless two pens crossing transmit the *product* of what each transmits alone, which is what makes ink subtractive rather than additive. Both probe the same code that ships, and a control sweep fails if any parameter turns out to do nothing.
>
> **Both plugins have been loaded and run in Resolume Arena 7.27.1, on macOS and on Windows** — they register with the right names and categories, expose all 50 controls with nothing truncated, render, and hold a factory preset through live rendering. **DaVinci Resolve Studio 21.0.2.4 lists the OpenFX build**, it renders correctly in an independent OFX host, and from v0.6.2 both plugins render as tools on the Fusion page of Resolve Studio 21.1. What is still unconfirmed is narrower: nobody has compared its output inside Resolve with the GPU's, so its CPU renderer is proven to run and not yet proven to match the GPU one pixel for pixel.
>
> Released at **v0.6.3**, which puts Export XML's files in Documents wherever Windows has moved it, OneDrive included, and starts Load XML's value in that folder. v0.6.2 fixed two things in the OpenFX build: every render on Resolve's Fusion page failed (and the generator now animates there), and choosing a factory preset crashed the host.
>
> This codebase was created with AI assistance, directed and reviewed by a human author.

Spirograph is a registered trademark of Hasbro, Inc. This project is not affiliated with, endorsed by, or connected to Hasbro. The name is used only to describe the kind of machine the plugin models.


Two plugins

- **Cogwheel** (a source) draws on its own sheet of paper.
- **Cogwheel Ink** (an effect) can use the clip below as the paper the pen draws on, as the ink the pen picks up, or both.

Both declare the same parameters, so a composition can be moved between them.

Start from a preset

The **Preset** dropdown is at the bottom of the list. Eight of them, and each is a recognisable *drawing* rather than a set of slider positions — which is only possible because the gear train is two integers.



Preset	What it is
Classic Rosette	96 and 52, four pens through four holes. The one everybody made first.
Three Lobes	96 and 32 mesh three to one, so the figure closes in a single turn. The pen never lifts, and a mesh half a tooth out of true walks it round the sheet.
Dense Web	105 and 64 share no factor at all: sixty-four turns and a hundred and five lobes, printed as a negative.
Flower	Outside the ring instead of inside — the petal shape rather than the rosette.
Slipping Gear	The ruined drawing, on purpose. A mesh well out of true and a three-tooth jump every few turns.
Wet Trail	Not a drawing: a trail. A fibre tip against a two-second fade.
Chalkboard	Graphite, a heavy tooth and a wide soft nib, printed as a negative.
Show the Gears	The machine on screen — ring, wheel, arm and pen — cranked slowly.

Keeping a look of your own

The presets are fixed — Resolume gives a plugin no way to add an entry to that dropdown while it is running, or to remember one between sessions. So there is no "save preset" button, and there cannot be one.

What there is instead is a pair of controls next to the dropdown. **Export XML** writes every control's current value to a timestamped file in a `cogwheel` folder in your Documents:

```
~/Documents/cogwheel/cogwheel-20260901-152822.xml
```

On Windows that is your Documents folder wherever Windows has put it. If OneDrive backs it up, that is `OneDrive\Documents\cogwheel`, not a second Documents folder beside it — the folder Explorer opens when you click Documents. (Before v0.6.3 it was always `C:\Users\<you>\Documents`, which on a OneDrive machine is not the one you look in.)

Each line carries both the number the plugin stores and the readable version of it, so the file is worth reading as well as keeping:

```
<parameter id="1" name="Ring Teeth" type="integer" value="96.000000" display="96t - 24
lobes"/>
<parameter id="8" name="Speed" type="standard" value="0.737000" display="1.63 turns/s"/>
```

Load XML, new in v0.3.0, reads one back. It is a file picker, and from v0.6.3 its value starts out as the folder Export XML writes to rather than empty. Choose a file and every control the file names is set from it, the sheet is wiped for the new machine, and the Preset dropdown drops to **Custom**, because the file is now the truth. The row next to it says `loaded`, `remembered`, or `failed - see log`. The full path — and any row the plugin could not place — goes to the diagnostics log, because sixteen characters of parameter display is not room for one.

Four things worth knowing:

- **Rows are matched by name, never by number.** A file written by the source loads into the effect and back, and a file from an earlier release still loads even though the controls have been renumbered since. A row naming a control that does not exist is skipped and logged.
- **Choosing the same file a second time does nothing.** A file is applied when the path *changes*, so a host that restates the same path every frame does not wipe the sheet every frame. To re-apply a file you have edited, pick a different one and then it again.
- **A loaded file is held the way a preset is.** Resolume goes on pushing the slider values it believed before the load; the plugin recognises those as the host repeating itself rather than as you editing, and keeps the file's values until you actually move something.
- **Reopening a composition does not re-read the file**, since v0.5.1. Resolume restores your saved parameters and then hands the plugin back the path that was in the picker; re-reading it there would put the file's values over the settings you saved, which is what #22 reported. A path arriving before the first frame, on controls that have already moved off their defaults, is the host restoring rather than you choosing, so the path is remembered and the row says `remembered`. Your composition wins, and picking a file yourself is unaffected.

The About block and the buttons are not settings and are not loaded, and a hand-edited value outside a control's range is clamped to the range rather than applied.

Moving any control a preset covers drops the dropdown back to **Custom**. That is the preset letting go, not an error.

The two numbers that matter

Ring Teeth and **Wheel Teeth** are the whole machine. Because gears mesh, the wheel cannot roll by anything other than a whole tooth, so everything about the figure follows from those two integers:

Ring	Wheel	Lobes	Turns to close
96	32	3	1
96	52	24	13
96	31	96	31

Drag either control and Resolume shows you the answer before you let go — the Ring reports how many lobes you are about to get, and the Wheel reports how many turns it will take to close.

Snap to Set restricts both to tooth counts a real Spirograph set carries. Leave it on unless you are hunting for something specific; the figures people recognise are the ones those particular integers make.

Pen Hole is which hole in the wheel the pen sits in. Near the rim gives long thin lobes; near the axle gives something close to a circle. **Snap to Holes** restricts it to the twelve modelled positions, which is what a real wheel offers.

Mesh decides whether the wheel runs round the inside of the ring (a rosette) or the outside (a petal shape).

A wheel as big as the ring, or bigger, cannot run round the *inside* of it — there is nowhere for it to go — so with Mesh on *Inside* and 100 wheel teeth against 96 ring teeth nothing is drawn. The two controls say so as you drag them: the Ring reads `too small` and the Wheel reads `too big`. Set Mesh to *Outside*, where a big wheel is fine, or choose a smaller wheel.

Why a drawing stops, and what to do about it

A closed figure retraces its own line for ever. That is not a bug and it is not something tuning fixes — it is what a Spirograph *is*. A drawing is finished when it is finished, and about ten seconds later nothing on screen is moving.

There are three ways out, and all three are things a person at the table actually does:

- **Creep** — the mesh is not quite true. A fraction of a tooth per turn precesses the figure so it never quite lands on itself, and the drawing keeps growing. This is on by default.
- **Skip** — a jumped tooth. Discrete, startling, and the classic way a real drawing is ruined. **Skip Size** is how far it jumps.
- **Layers** — when a figure closes, lift the pen, move to another hole, change the pen and draw the next one on top. That is how the multicoloured Spirograph drawing everybody remembers is actually made. **On Closing** decides what moves; **Wipe Sheet** starts a fresh sheet when the whole stack is done.

If the picture has gone still, one of those three is off.


There is a fourth way, new in v0.5.0, and it is the opposite of the other three: **On Closing → Keep Going**. When the figure comes home nothing happens at all. The pen stays down, the same pen in the same hole carries on round, and with **Creep** on the figure keeps precessing for as long as the crank turns — the growing rosette, kept. A closure is not an event under Keep Going: nothing is counted, nothing is wiped, **Layers** has nothing to do (it reads `keeps going` to say so), and **Fade by Figure** has nothing to settle. With the ordinary **Fade** the drawing reaches whatever balance the fade rate sets and stays there.

A stack of one **Layer** also keeps the pen down, but it still *counts* each closure — which with Fade by Figure on settles the drawing so far and starts it fading. Keep Going does not.

Selecting Keep Going holds **the figure that is on the paper**, since v0.5.1. Which wheel and which hole a figure uses is worked out from the seed, the layer number and On Closing itself, so switching to Keep Going part-way through a run used to lose two of those and fall back to what you originally threaded — a different figure, on the frame you asked it to stop changing (#24). It now latches the layer and the mode that produced what you are looking at. Switching back off hands the drawing to the live sequence again at the next closure.

There is a fifth, new in v0.6.0, and it is not a way out so much as a way of letting the drawing choose: **Unless Faded**, the switch under On Closing. With it on, a figure closes only if it was drawn inside the **Fade** time. One that took longer has faded from behind the pen by the time the pen comes home — there is no whole figure on the paper to close — so it keeps going instead, exactly as if On Closing said Keep Going, and is asked again the next time round. One that was quicker closes as On Closing says. So with a single fade setting the quick wheels stack and the slow ones keep going: at the default crank a 96/32 comes home in two seconds and stacks under a ten-second fade, while a 96/31 takes a minute and never does. Turn Fade up past a figure's lap and it closes the next time it comes home; turn it down and the stack stops growing. The readout next to the switch says the number it is working to — `longer than 12s` — so you can see which figures will close without doing the sum.

It needs **Fade** above zero: with no fade nothing has faded and every figure closes, and the readout says `no fade: closes`. The rule is the same under **Fade by Figure**, where the figure being drawn does not literally fade — a figure slower than the fade keeps going in both modes, so the switch means one thing whichever fade you are using. It came out of #25, which asked exactly this question as a thought experiment.



The same wheel, the same two-second fade, the same frame. On the left the figure took longer than the fade to draw, closed anyway, and the pen has lifted twice — red, then blue, then green, each fading behind the next. On the right it kept going: the same red pen, never lifted, the figure precessing under Creep with the fade following it round.

The pen

Pen Type is a real distinction between two real classes of pen, not a look.

- A **ballpoint**'s ball rolls, so it lays down ink per unit of *distance*: a line is the same darkness however fast your hand moved. That is what came in the box, and it is the default.
- A **fibre tip** feeds by capillary action, per unit of *time*, so it blooms wherever the pen slows down — which at a cusp is a great deal.

Blend is how new ink meets the ink already on the sheet, and each entry is a real thing you can put in the pen hole rather than a blend mode off a menu:

- *Multiply* is transparent ink — what every pen in the box does. Absorptions add, crossings darken, and red over blue is the near-black it is on the table. This is the default and the only one the next section describes.
- *Cover* is opaque pigment — a paint marker. New ink hides what is under it, a crossing is the colour of whichever pen came second, and a pen never darkens beyond its own colour however often it crosses itself. Set **Pens** to *Ink Colour* and the **Ink** sliders to white, or to the paper colour, and Cover is white-out.
- *Lift* is an eraser in the pen hole. The pen's colour is ignored and the figure is drawn in whatever was underneath before the ink was laid — which on a clean sheet is nothing at all.

If what you wanted was *add* — a line that brightens the sheet — that is **Print → Negative**, because ink cannot add light. All three compose exactly with **Fade by Figure**, and a preset sets Blend along with the rest of the pen.

Flow is how dark the line is. It is multiplied by the nib's width internally, so widening the nib does not lighten the line — a broader pen delivers proportionally more ink, which is what makes it broader rather than blurrier.

Nib is the line's width, as a fraction of the sheet, so it is the same line at every output resolution. **Pressure** is how much a pressed nib spreads.

Pens chooses what the layers are drawn with — *Four Pens* is the set that came in the box. *Ink Colour* uses the **Ink Red**, **Ink Green** and **Ink Blue** sliders instead.

Ink is subtractive, and what follows from it

The sheet accumulates optical density, and what you see is the paper through it. A second pen crossing the first therefore gives the *product* of the two transmissions — the muddy near-black it is on the table — rather than the bright sum an additive renderer would produce. A pen that lingers lays down more.

Two consequences worth knowing:

- **Changing the paper colour or the palette does not spoil what is already drawn.** The sheet never held a colour to be wrong about.
- **Ink can only ever darken paper.** A pale line on a dark ground is not something the machine can make. **Print → Negative** is the honest route to it: a drawing, photographed and printed the other way up.
- **Black paper hides the drawing.** Turn the **Paper** sliders down to black and the ink has nothing to darken, so the whole sheet goes black — which is Beer's law, not a fault. If what you wanted was to key the paper out and composite the line over other layers, that is what **Clear Paper** is for.


Clear Paper takes the paper away altogether. The output is the ink on a clear sheet, with an alpha channel: composite it over anything in Resolume and the line shows in its own colour, a black pen darkens whatever is behind it exactly as ink would, and over white you get precisely the drawing on white paper. The paper colour, **Grain** and **Paper from Clip** do not apply while it is on, because there is no paper. On the effect the ink goes over the clip and the clip keeps its own alpha.

Grain is how much of the paper's tooth you can see. **Tooth** is a different question — how unevenly the sheet *takes* ink. Smooth board takes ink evenly and shows no grain; cartridge does both.

Fade is the one control in the plugin that is not something the machine can do. A drawing does not fade. It is here because a VJ needs the sheet to clear, and at zero it does not fade at all, which is what paper does.

Fade by Figure decides what the fade acts on. Off — which is how it has always behaved — the fade acts on the sheet, every frame. Ink laid down at the start of a figure has therefore been fading for longer than ink laid down at its head, so the line carries a gradient along its own length: it is palest where the pen started and darkest where the pen is now. On, the figure being drawn does not fade at all. It joins the drawing at the moment it closes, and fades from then on as one object, so a figure is a single even weight of line and the ones behind it lift away whole.

It needs **Fade** above zero to mean anything: with no fade there is nothing for it to change the shape of. Turning it off again does not lose anything — everything that had settled comes straight back onto the sheet.



The same machine and the same fade, at the same frame. On the left the blue figure is being drawn and is palest where the pen started; on the right it is one weight of line all the way round, and the red figure behind it has lifted away evenly rather than in a gradient.

Cranking, and syncing to the music

Speed is turns of the ring per second.

> **Renamed in v0.2.0.** This control was called **Crank** in v0.1.0. Every other plugin in the range calls it Speed, so it now does too. Two things follow, and both bite silently: a composition saved against v0.1.0 loses whatever Crank was set to and opens at the default, and any OSC or MIDI mapping pointing at "Crank" stops arriving. Re-point the mapping and re-save the composition once, and that is the end of it.

Sync overrides it: choose 1, 2, 4 or 8 bars and the figure is given that many bars to complete, whatever this particular train's turn count is. So a thirteen-turn figure and a one-turn figure both land on the bar line together. That is the only sensible reading of "one figure per phrase".

New Sheet throws the drawing away and starts again. It sits at the very top of the parameter list, above every group, so it is always in reach — clearing the paper is the one thing you want mid-show and it used to be folded away inside the Crank group.

Detail is how finely the pen path is walked — 360, 1440 or 5760 steps a turn. It is a cost dial with a visible symptom: at *Draft* a big figure is faintly polygonal. It does **not** change how much ink goes on the sheet.

Show Gears puts the ring, the wheel, the arm and the pen on screen, with the real tooth counts, so they can be counted. It is the quickest way to explain the plugin to somebody standing next to you.

In OpenFX hosts

Copy `Cogwheel.ofx.bundle` to:

- **macOS** — `/Library/OFX/Plugins`
- **Windows** — `C:\Program Files\Common Files\OFX\Plugins`
- **Linux** — `/usr/OFX/Plugins`

⚠️ **On macOS it must be `/Library/OFX/Plugins`, which needs an administrator.** Putting it in `~/Library/OFX/Plugins` is **silently ignored** — the plugin simply never appears, with nothing logged and no error, which looks exactly like a broken plugin.

Two things behave differently there, both stated rather than hidden:

- **The OpenFX build renders on the CPU.** There is no OpenGL context to be had in an OFX host, so it is built for offline rendering rather than for live use.
- **A drawing is history, so it replays from the beginning.** A linear render costs nothing per frame beyond that frame's own strokes. Scrubbing *backwards* through a long drawing is slow, and gets slower the further in you are. There is no warm-up window that would fix this: one would produce a different drawing, missing everything laid down before the window opened. Render forwards.

Sync works off a fixed 120 bpm in OpenFX, because OFX carries no transport tempo.

Export XML and **Load XML** are here too. Resolve has its own presets, so they exist mainly to share a look with the Resolume build: a file written by either loads in the other. In an OpenFX host Load XML is a file path with a browse button.

If it looks wrong

The picture has stopped moving. The figure has closed. Turn up **Creep**, raise **Layers**, or add some **Skip**. See "Why a drawing stops" above.

Everything is solid black. Flow is too high for the crank rate. A dense figure crosses itself constantly and every crossing darkens; *Dense Web* runs at a deliberately light flow for exactly this reason.

The drawing is off the edge of the frame. Check **Size** and **Centre**. Size is the ring's radius as a fraction of the frame height, so at 1.0 the ring exactly fills it.

The lines look polygonal. Detail is on *Draft*. Move it to *Normal*.

Nothing draws, and Blend is on Lift. An eraser on a clean sheet takes nothing off. Set Blend back to *Multiply*.

Nothing draws, and Wheel Teeth reads `too big`. The wheel is as big as the ring or bigger and **Mesh** is on *Inside*. Set Mesh to *Outside* or choose a smaller wheel. The log says the same.

Everything went black when I set the paper to black. Ink only darkens paper, so on black paper there is nothing to see. Use **Clear Paper** to key the sheet out, or **Print → Negative** for a pale line on a dark ground.

Nothing appears at all in Resolume. Check `~/Library/Logs/cogwheel/` (macOS) or `%LOCALAPPDATA%\cogwheel\logs\` (Windows). A shader that will not compile, or a sheet that would not allocate, both look like "it does nothing" from outside and both say so there.

A control does nothing. Some are conditional: **Skip Size** needs **Skip Chance** above zero, **On Closing** and **Pens** need **Layers** above one, **Layers** and **Pens** do nothing under *Keep Going* because the pen never comes off the paper, **Unless Faded** needs **Fade** above zero and a figure that takes longer than it to draw (its readout says which), the **Ink** sliders only apply when **Pens** is set to *Ink Colour*, and **Ink from Clip** / **Paper from Clip** exist only on the effect.
